

BRUHAT BANGALORE MAHANAGARA PALIKE

3BMP/2016-17/RD/WORK_INDENT24260/CALL-1

APPROVED SCHEDULE - B

EE/TP/BBMP/E-PMT/21/2016-17, Date: 14.02.2017


Improvements to roads and drains in Padma tent area in ward no.07, Byatarayanapura

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				N NAVEEN	
				In Figures	In Words
1	340.1	KSRB 2-2.2:Earth work excavation for foundation of building, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ORDINARY soil not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications and direction of the Engineer-in-charge.	Cum	78.17	Rupees Seventy Eight and Seventeen Paise Only
2	45.67	KSRB 4-1.3: Providing and laying in position plain cement concrete of nominal mix 1:4:8 using 40mm and down size graded granite metal machine mixed, concrete laid in layers not exceeding 15 cms. Thick well compacted in foundation and plinth, including cost of all materials labour, HOM of machinery, curing complete as per specification.	Cum	4766.36	Rupees Four Thousand Seven Hundred Sixty Six and Thirty Six Paise Only
3	0.9	KSRB4-1.6: Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs, with 20 mm and down size graded granite metal coarse aggregates @ 0.69 cum and fine aggregates @ 0.459cum, machine mixed concrete laid in layers not exceeding 15 cms, thick well compacted, in foundation, plinth and cills including cost of all materials, labour HOM machinery curing complete as per specifications.	Cum	5161.27	Rupees Five Thousand One Hundred Sixty One and Twenty Seven Paise Only
4	73.74	KSRB 4.2.2: Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastizers @ 3lts conforming to IS 9103-1999 RE affirmed - 2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, stair case lintels, retaining walls return walls, walls(anythickness) including attached plasters columns piers abutments pillars posts struts buttresses string or lacing courses parapets copings, bed blocks, plain windows cills fillets etc., including cost of all materials labour HOM of machinery curing complete as per specifications.	CUM	5826.12	Rupees Five Thousand Eight Hundred Twenty Six and Twelve Paise Only
5	4.79	KSRB 4-9-2:Providing and fabricating TMT . Steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking,placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design(laps and wastage shall not measured and paid) cost of materials. labour. HOM of machinery complete as per specifications . (Page NO 17, Itm. NO. 4.46.2)	tonne	55767.38	Rupees Fifty Five Thousand Seven Hundred Sixty Seven and Thirty Eight Paise Only
6	955.2	KSRB 4-6.4: Providing and removing centering, shuttering strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness including attached pilasters, buttressed, plinth and string courses cost of all materials, labour complete as per specifications	Sqm	287.64	Rupees Two Hundred Eighty Seven and Sixty Four Paise Only
7	10	KSRB 4-48: Providing and laying in cement concrete using 20mm and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) for RCC works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges	Cum	5952.11	Rupees Five Thousand Nine Hundred Fifty Two and Eleven Paise Only
8	2.7	KSRB 5.3-1:Providing and constructing granite /trap/basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at two m apart in each course including cost of materials, labour, curing etc., complete as per specifications.	Cum	3248.64	Rupees Three Thousand Two Hundred Forty Eight and Sixty Four Paise Only


Signature of the contractor

Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				N NAVEEN	
				In Figures	In Words
9	42	KSRB 5.3-1:Providing ruled pointing of course stone msonry with cement mortar 1:3 20 mm deep, after raking joints to depth of 20 mm nicley lining, including cost of materials, labour, curing etc., complete as per specifications and directions of the engineer-in-charge.	Sqm	33.5	Rupees Thirty Three and Fifty Paise Only
10	21	Providing and fixing 10cms thick pre cast RCC covering slab using reinforced cement concrete M20 mix with stone aggregate 20mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specifications	Sqm	1725.84	Rupees One Thousand Seven Hundred Twenty Five and Eighty Four Paise Only
11	7.56	Providing and fixing 20 cm thick pre cast RCC covering slab using reinforced cement concrete M 20 mix with stone aggregate 20 mm and down size including centring shuttering reinforcement and bar bending machine mixed concrete laid in layers not exceeding 15 cm thick wellcompacted cost of all materials labour curing complete as per specification	Cum	4804.34	Rupees Four Thousand Eight Hundred Four and Thirty Four Paise Only
12	340.1	KSRRB M100-1 Loading and unloading of stone boulder/stone aggregates/ sand/ kanker/ moorum. KSRRB M100-1:Placing tipper at loading point loading with front end loading, dumping turning for return trip, excluding time for haulage and return trip complete as per specification	Cum	89.13	Rupees Eighty Nine and Thirteen Paise Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92


06/05